

RCC work at main gate road entry & PCC work in the University.

Sr. No	Item Name	Qty.	Unit	Basic Price in Rs.	Amount
	H.S.R Item:-				
1.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - Allwork below plinth level and up to Floor IV level: 1 : 1 ½: 3 (1 Cement: 1 ½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size) HSR 6.1.1	3.93	Cum		
2.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - Allwork below plinth level and up to Floor IV level: 1 :4: 8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size) HSR 6.1.6	7.62	Cum		